BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified SCHDULE-B

Name of Work: Improvements and Construction of CC Roads at Jain Temple 1st, 2nd, 3rd, 4th, 5th & cross roads & MTS Colony Main road in Dasarahalli ward No:15

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Removing B.S.Slabs and stacking etc complete	Sqm	788.94	55.34	Rupees Fifty Five and Thirty Four Paise Only
2	Earthwork excavation by manual means in ordinary soil involving an avegage horizontal throw up to 2 meters and an average lift up to 0.5 m, excavated surface leveled and sides neatly dressed the diposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	487.00	73.20	Rupees Seventy three and Twenty Paise Only
3	Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	788.94	67.84	Rupees Sixty seven and Eighty Paise Only
4	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials	Sqm	87.48	1347.36	Rupees One thousand Three hundread Forty Seven & Thirty Six Paise Only
5	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of Machinery, screed Vibratory, Power Floater, blade and disc etc., with all lead and lift	Sqm	2842.40	80.34	Rupees Eighty and Thirty four Paise Only
6	Providing Concrete Groove cutting for width of 5mm to 10mm and depth 80mm100mm including cost of cutting machine generator & HOM of machinery, including cost of blade coolant etc., including cleaning of groove & Providing sand and hot bitumen fillars, and fillars metal etc., including cost of conveyance of all materials, labour lead and lift charges and all other incidental charges as per drawing and as per specifications.	rmt	212.00	102.65	Rupees One Hundread Two and Sixty five Paise Only

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73.

7	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and	Cum	131.49	233.51	Rupees Two Hundread Thirty three and fifty one Only
8	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Sqm	65.75	4106.17	Rupees Four thousand One Hundread Six and Seventeen Paise Only
9	Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of .. contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications.	Cum	405.96	5622.70	Rupees Five thousand Six Hundread Twenty two Only
10	Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Sqm	14.20	57098.97	Rupees Fifty seven thousand Ninety and Ninety seven Paise Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km. Qty Executed Upto 125%	Sqm	150.19	63.36	Rupees Sixty three and Thirty six Paise Only
	Qty Executed above 125%		468.30	68.04	Rupees Sixty eight and four Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division